

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21642-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 7-22S-16W  
1550 feet from N Section Line, 635 feet from E Section Line  
Lease Name: EAKIN Well #: 4-7  
County: PAWNEE Total Vertical Depth: 4002 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 445 UNION BOULEVARD SUITE 208  
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3720		WITH 2 SX CMT
CIBP		3890		
PROD	5.5	4000	1732	WITH 250 SX CMT
SURF	8.625	1027		WITH 415 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2013 1:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES Phone: (785) 623-1524

Proposed Plugging Method: SET CIBP @ 3810' WITH 2 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2013 2:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3720' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 40 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3921	3924		
3892	3900		
3867	3872		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

KCC WICHITA

JUL 18 2013

RECEIVED

District: 01

Signed Richard M. Lacey  
7/19/13 (TECHNICIAN)

RECEIVED

JUL 16 2013

KCC DODGE CITY

*Handwritten initials*