

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21290-00-00
Spot: NENENW Sec/Twnshp/Rge: 10-32S-22W
5016 feet from S Section Line, 3083 feet from E Section Line
Lease Name: CHARLOTTE Well #: 1
County: CLARK Total Vertical Depth: 6887 feet

Operator License No.: 34438

Op Name: PRICE, TRACY DBA BARRON RESOUR
Address: 301 S WASHINGTON PO BOX 276
PROTECTION, KS 67127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4650		WITH 2 SX CMT
COND	20	65		
PROD	5.5	5095	2630	WITH 320 SX CMT
SURF	8.625	811		WITH 350 SX CMT

Handwritten notes:
KCC
7/19/13

Well Type: SWD UIC Docket No: D28581.0 Date/Time to Plug: 04/05/2013 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4650' WITH 2 SX CMT. PLUG AT 850' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/27/2013 5:30 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

4/5/13: KLIMA WELL SERVICE PULLED 95000# BUT COULD NOT GET THE SLIPS LOOSE. SET CIBP @ 4650' WITH 2 SX CMT. KLIMA WILL RIG DOWN & QUALITY WELL SERVICE WILL EVENTUALLY RIG UP TO FINISH THE PLUG JOB. 6/26/13: QUALITY WELL SERVICE RIGGED UP & CUT THE 5 1/2" CASING AT 2630'. 6/27/13: 1ST PLUG AT 875' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4950	4955		
4700	4730		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

JUL 05 2013

RECEIVED

District: 01

RECEIVED
JUL - 1 2013
KCC DODGE CITY

Signed Eric MacLaren (TECHNICIAN)
cc to UIC 7/19/13 7/28/13

Handwritten initials: RM7