

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23800-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 23-15S-17W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: TIEDEMANN Well #: 2  
County: ELLIS Total Vertical Depth: 3565 feet

Operator License No.: 33864  
Op Name: HABIT PETROLEUM, LLC  
Address: 639 280TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3564		125 SX
SURF	8.625	215		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2013 12:00 AM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: IRVIN E HASELHORST Company: SCHIPPERS OILFIELD SERVICES, L Phone: (785) 623-1154

Proposed Plugging Method: Ordered 350sx 60/40 Poz 45 gel cement and 300# hulls.  
DV@ 1122' circulated to surface. 1984  
Casing leaks

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 06/29/2013 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

6/28/2013 Ran tubing to 3000' and pumped 50sx cmt w/150# hulls.  
Pulled tubing to 1500' and pumped 200sx cmt w/100# hulls. No circulation. Shut down.  
6/29/2013 Ran tubing and tagged at 2300'. Pumped 140 sx cmt to circulate to surface.  
POOH.  
Tied onto 4 1/2" and pumped 20 sx cmt. 250 psi shut in.  
Hooked to backside and pressured to 300 psi.


Perfs:

Remarks: SCHIPPERS OILFIELD SERVICES #1055

Plugged through: TBG

District: 04

Signed

  
7/18/13

(TECHNICIAN)

KCC WICHITA

JUL 17 2013

RECEIVED