

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101 - 20,908-0000

NW NW NE , Sec. 24 , T 19 S, R 30 W/X

330 feet from N/X section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6735

Lease Name Nuss Well # 1

Operator: Southwestern Energy Prod. Co.
Name & 1001 N.W. 63rd, Suite 200
Address Oklahoma City, OK 73116

County Lane

Well Total Depth 4710 feet 153.07

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 7:00 pm Day: 28 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO John Crowe

(company name) DaMac (phone) 316-793-7569

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1140' with 50 sx cement

3rd plug at 690' with 50 sx cement

4th plug at 270' with 40 sx cement

5th plug solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 10 sx Signed Steve Durant

8th plug to circulate mousehole with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 pm Day: 28 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1140' with

50 sx cement, 3rd plug at 690' with 50 sx cement, 4th plug at 270' with 40 sx cement,

5th plug and 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 7th plug to circulate rathole with 10 sx cement, 8th plug to circulate

mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
MAR 07 1984
3-7-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~was~~ / did not) observe this plugging.

INVOICED

Signed Steve Durant
(TECHNICIAN)

DATE
INV. NO. 0620