

To: 1 080124  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION APP.  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-20,901-0000  
NE SE NW, SEC. 2, T 20 S, R 29 WXX  
1640 feet from NXXK section line  
2300 feet from WXXK section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 31645  
Operator: JHS Energy, Inc.  
Name:  
Address 1720 S. Bellaire St., Ste. 1209  
Denver, CO 80222

Lease Name Monroe "B" Well # 1  
County Lane 152.23  
Well Total Depth 4684 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing License Number 6901  
Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 9 a.m. Day: 22 Month: 5 Year: 19 97  
Plugging proposal received from Bill Richardson  
(company name) JHS Energy, Inc. (phone) 303-757-8811

Work: 4 1/2" at 4683' w/175 sx cement, PBSD 4618', Perfs at 4355-76', Tubing parted, casing leak at approx. 1800'  
1st plug run tubing to 1600', pump 40 sx cement with 200 lbs. hulls, 40 sx cement, pull tubing,  
2nd plug cut casing and fill with cement.

6-2-97

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4:30 p.m. Day: 22 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT Recovered all of the rods and 1800' of tubing. Top of tubing at 1800'.  
Tubing was parted at 1800'

Cut casing at 1200' and ran tubing to 1600', pumped 40 sx cement with 200 lbs. hulls and 40  
sx cement. Pulled tubing and cut casing at 600', pumped 80 sx cement. Well on vacuum.  
Pulled casing out of hole and let set 3 hrs. Ran tubing in, tagged at 350'. Loaded hole with  
19 bbl. and pumped 50 sx cement. Pulled up to 60' and pumped 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (and XXXXX) observe this plugging.

DATE JUN 06 1997  
INV. NO. 48241

Signed Kevin P Strube (TECHNICIAN)