

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 009-20,767-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR SID TOMLINSON KCC LICENSE # 6412
(owner/company name) (operator's)

ADDRESS 424 NW 42 CITY Oklahoma City

STATE OK ZIP CODE 73118 CONTACT PHONE # (405) 521-1852

LEASE Burmeister WELL# 2 SEC. 27 T. 16 R. 11 (East/West)

-NE - SW - SE SPOT LOCATION/0000 COUNTY Barton

990 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

1720 FEET (in exact footage) FROM (E) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 365 CEMENTED WITH 225-circulated SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3414 CEMENTED WITH 125-Top cement SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3368-83 Arbuckle @ 2850 by bond log.

ELEVATION 1941 T.D. 3415 PBD 3395 ANHYDRITE DEPTH 762
(Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

Squeezed 5 1/2 csg w/225 sx at 568' (40' below base Cedar Hills)-500# pressure
PROPOSED METHOD OF PLUGGING

Pmp 50 sx in braden head annulus. Pmp in 5 1/2 csg with 40 sx(525'), 37 bbls

gel spacer(1500'), 125 sx(1650') at top. Use 60/40 Poz w/ 10% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Sid Tomlinson 405-521-1852 PHONE# ()

ADDRESS City/State

PLUGGING CONTRACTOR KCC LICENSE #
(company name) (contractor's)

ADDRESS PHONE # ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/18/96 AUTHORIZED OPERATOR/AGENT: Sid Tomlinson
(signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 23, 1996

Sid Tomlinson
424 NW 42
Oklahoma City OK 73118

Burmeister #2
API 15-009-20,767-0000
990 FSL 1720 FEL
Sec. 27-16S-11W
Barton County

Dear Sid Tomlinson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200