

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY NESS SEC. 24 TWP. 20S RGE. 26W E/W
Location as in quarters or footage from lines:
NE SW SE

Lease Owner Chief Drilling Co., Inc.
Lease Name Jones Well No. #1
Office Address 905 Century Plaza Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
Date Well Completed 7-16-82
Application for plugging filed 7-16-82
Plugging commenced 7-16-82
Plugging completed 7-16-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Dry hole
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4468

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8 255'	set @ 264'		20#		

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged w/135 sx. 50-50 pos mix, 4% gel, 3% c.c.
70 sx. @ 1020', 40 sx. @ 270', 10 sx. @ 40', 10 sx.
in Rat hole, 5 sx. in mouse hole, Started @ 11:00 a.m.
Completed @ 1:00 p.m. Steve Durrant, Belpree, State Plugger

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WARRIOR DRILLING CO.

STATE OF Kansas COUNTY OF Sedgwick, ss.
F.W. Shelton, Jr., (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice Pres.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 82

RECEIVED 07-22-1982
STATE CORPORATION COMMISSION
JUL 22 1982
CONSERVATION DIVISION
Wichita, Kansas

MARTHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 4-15-85

Martha E. Gustin
Martha E. Gustin Notary Public.

My Commission expires _____

WELL LOG

JONES #1
NE SW SE SEC. 24-20S-26W
NESS COUNTY, KANSAS

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

CONTRACTOR: Warrior Drilling Co.
CASING RECORD: Ran 6 jts. new 20# 8 5/8", 255'
set @ 264' cemented w/175 sx.
common quick set, plug down @ 3:00 p.m.

COMMENCED: 7-06-82
COMPLETED: 7-16-82

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>	
			2436	GR.
Rock	0	381	2440	D.F.
Surface Clay	381	675	2443	K.B.
Sand & Clay	675	1045		
Sand & Shale	1045	1648		
Anhydrite	1648	1681		
Shale	1681	2860		
Shale & Lime	2860	3405		
Lime & Shale	3405	4160		
Shale & Lime	4160	4420		
Lime	4420	4468		
RTD	4468			

D & A

Plugged @ 4468' RTD w/135 sx. 50-50 pos mix.
4% gel, 3% c.c., 70 sx. @ 1020', 40 sx. @ 270'
10 sx. @ 40', 10 sx. in rat hole, 5 sx. in mouse
hole,

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1982
07-22-1982
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the
Driller's Log of the well drilled in the NE SW SE SEC. 24-20S-26W
NESS County, Kansas, to the best
of my knowledge and belief.

CHIEF DRILLING CO., INC.

F. W. Shelton, Jr.
F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 19th day of July 1982.



MARTHA E. GUSTIN