


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ness County, Sec. 16 Twp. 20 Rge. (E) 26 (W)

Location as "NE/CNW&SW" or footage from lines. NE NE SW/4
Lease Owner Armer, Inc.
Lease Name Jones Well No. 1
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 8 19 55
Application for plugging filed May 7 19 55
Application for plugging approved May 7 19 55
Plugging commenced May 7 19 55
Plugging completed May 8 19 55
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5140 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	285'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, set 1/3 sack hulls and
Halliburton plug at 280 ft. with 20 sacks cement thru drill pipe.
Mudded hole to 35 ft., set 1/3 sack hulls, plug and 10 sacks
cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Armer, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

RECEIVED
DIVISION
1955
05-12-1955

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) or (agent or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN to before me this 10 day of May, 19 55

My commission expires February 13, 1955.

Rose Furey Notary Public.

PLUGGING
MAY 16 20 55
117 39

KANSAS GEOLOGICAL SOCIETY 15-135-00092-00-00
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Armer, Inc.

SEC. 16 T. 20 R. 26E
 LOC. NE NE SW

FARM Jones

NO. 1

TOTAL DEPTH 5140

COMM. 4/15/55

COMP. 5/8/55


COUNTY Ness

KANSAS

SHOT OR TREATED

CONTRACTOR Armer, Inc.

ISSUED



CASING

20	10	
15	8	285'
12	6	
13	5	

ELEVATION 2554 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay	40
Shale & Shells	285
Shale	460
Shale & Shells	1225
Anhydrite	1240
Shale, Red Bed & Shells	1800
Shale & Shells	2075
Shale & Lime	2245
Shale	2440
Shale & Lime	3960
Lime	4260
Shale & Lime	4305
Lime	4442
Shale & Lime	4525
Lime	4556
Lime & Chert	4581
Lime	4655
Shale & Lime	4730
Lime & Chert	4785
Chert	4820
Lime	4859
Chert & Lime	4968
Chert	4989
Chert & Lime	5050
Cherty Lime & Shale	5085
Lime & Chert	5140

FORMATION TOPS

HEBENER	3889	Mississippi	4561
TORONTO	3907	MISSISSIPPI DOLOMITE	4593
LANSING	3929	MISSISSIPPI OSAGE	4719
BASE KANSAS CITY	4333	MISSISSIPPI GILMORE CITY	4835
HARMATON	4380	VIOLA	4954
CHEROKEE	4480	SIMPSON SHALE	5074
PENNSYLVANIAN CONGLOMERATE	4542	SIMPSON SAND	5078
		ARBUCKLE	5088

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RECEIVED
 STATE GEOLOGICAL SURVEY

ARMER, INC.

05-12-1955
 CONSERVATION DIVISION
 Wichita, Kansas

By *C. C. Spruick*

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

PLUGGING

Subscribed and sworn to before me, a notary public, in and for said County and State this 9th day of May, 1955.

SEC. 16 T. 20 R. 26E
 PAGE 11 LINE 29

Rose Furey
 Notary Public

My Commission expires February 13, 1956.