

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,747-00-00

LEASE NAME Johnson

WELL NUMBER 1-13

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 13 TWP. 20S RGE. 26 (X) or (W)

COUNTY Ness

Date Well Completed D&A

Plugging Commenced 6/16/93

Plugging Completed 6/17/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ensign Operating Co.

ADDRESS 621 17th St., #1800, Denver, CO 80293

PHONE# (303) 293-9999 OPERATORS LICENSE NO. 04782

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/17/93 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From 0	To 351	Size 8 5/8	Put In 351	Pulled out 0
				4 1/2	4535	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Set CIBP on wireline @ 4442' - dumped 2 sx cmt on CIBP. Ran free point survey & cut off csg @ 2600'. 225 sx 60/40 Poz A/CI "A", 6% gel & 1/4#/sk flocele as follows: 50 sx cmt @ 1880', 80 sx cmt @ 970', 50 sx cmt @ 340', 25 sx cmt F/100' to 3', cut off & capped surf csg 3' below GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service License No. 6907

Address P O Box 458, Ness City, KS 67560-0458

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ensign Operating Co.  
City & \_\_\_\_\_

STATE OF Colorado COUNTY OF Denver, ss.

Conni Smith

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Conni Smith

(Address) 621 17th St., #1800, Denver, CO 80293

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of June 1993

Pamela S. Campbell  
Notary Public

My Commission Expires: 9/30/94

0628-1993  
RECEIVED  
KANSAS CORPORATION COMMISSION  
Wichita, Kansas  
Form CP-4  
Revised 05-88