


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County. Sec. 2 Twp. 20S Rge. 26 (2x (W))  
Location as "NE/CNW%SW%" or footage from lines. C NE/4 SW/4  
Lease Owner Kenneth Rupp  
Lease Name Hinkel Well No. 1  
Office Address 522 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9/19/60 19  
Application for plugging filed 9/19/60 19  
Application for plugging approved 9/19/60 19  
Plugging commenced 9/19/60 19  
Plugging completed 9/19/60 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4733 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	506'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 506', cemented w/20 sax through drill pipe. Mud to 40' - hulls - plug - cement to base of cellar - hulls in rat hole - 1 sax cement.

STATE OF KANSAS  
SEP 23 1960  
CONSERVATION DIVISION  
Wichita, Kansas  
09-23-1960

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. F. Carter, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) J. F. Carter, Jr.  
522 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 60

My commission expires May 11, 1963  
Marguerite Pickey Notary Public.



15-135-00137-00-00

CONTRACTOR'S WELL LOG

Kenneth Rupp No. 1 Hinkel  
C NE SW Sec. 2-20S-26W  
Ness County, Kansas

Elevation: 2602 D.F.  
2605 R.B.

Contractor: Rupp-Ferguson Oil Co.  
Commenced: 9-3-60  
Completed: 9-19-60

Set 8 5/8" @ 506' w/225 sax

Figures Indicate Bottom of Formation

40	surface clay	3855	cherty lime and shale
102	clay and shale	3977	lime (sandy streaks) & shale
110	shale, lime and shells	4015	lime, shale and chert
300	shale and shells	4360	lime
506	shale and clay	4590	lime and shale
550	shale	4606	lime, shale, chert
1060	shale and sand streaks	4710	lime and shale
1213	red bed and shale and sand	4733	T.D. lime, shale and chert
1250	Anhydrite and shale		
1475	shale and sand		
1690	shale and shell		
1853	shale		
1866	Anhydrite		
1878	shale		
1891	Anhydrite		
2290	lime and shale		
2485	shale, lime and shells		
2875	lime and shale		
3023	lime and shale streaks		
3335	lime and shale		
3395	shale and lime streaks		
3683	shale and lime		
3815	chalky lime and shale		

RECORDED  
STATE CLERK  
SEP 22 1960  
COMMISSIONER'S DIVISION  
Wichita, Kansas  
09-23-1960

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

I, J. F. Carter, Jr., Petroleum Engineer for Rupp-Ferguson Oil Co., do hereby certify the above and foregoing to be a true and correct copy of the log of the No. 1 Hinkel well.

*J. F. Carter, Jr.*  
J. F. Carter, Jr.

Subscribed and sworn to before me this 22nd day of September, 1960

*Marguerite Dickey*  
Marguerite Dickey, Notary Public

My Commission Expires May 11, 1963.