


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 1 Twp. 20 Rge. 26 E/W
Location as "NE/CNW/SW" or footage from lines
App. NE SW SE
Lease Owner Pickerell Drilling Co.
Lease Name Betz I #1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Flat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/6/79 19
Plugging completed 7/13/79 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4586
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	220	none
				1 1/2"	4581	2570'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4480' and ran 4 sacks cement. Loaded hole, shot pipe at 3580', 3488', 3362', 3188', 3018', 2838', 2709', 2583', pulled 69 joints and tallied pipe. Allied pumped 2 sacks hulls, 10 sacks gel, 70 sacks cement, 5 sacks gel, 2 sacks hulls, plug and 70 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 19 79

My commission expires



Margaret Melcher
Notary Public.

COMPANY: PICKRELL DRILLING COMPANY
205 LITWIN BLDG.,
WICHITA, KS. 67202
LOCATION: BETZ "I"
APR NE SW SE 1-20S-26W
NESS CO., KANSAS
CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Rotary Drilling Commenced 3-1-78
Rotary Drilling Completed 3-24-78

CASING RECORD: Surf casing 8 5/8" set at 220' with 150sx.
Prod casing 4 1/2" set at 4581 w/150 50-50 pox & 50 common

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Shale	223
Shale	1000
Shale	1245
Sand	1465
Shale	1675
Shale	1805
Shale	2150
Shale & Lime	2315
Shale & Lime Stringers	2423
Shale & Lime	2590
Shale & Lime	2765
Lime & Shale	2935
Lime & Shale	3120
Lime & Shale	3270
Shale & Lime	3445
Lime	3595
Lime & Shale	3765
Lime & Shale	3925
Lime & Shale	3985
Lime	4075
Lime	4150
Lime	4250
Lime	4340
Shale & Lime	4415
Lime	4478
Lime	4500
Lime	4520
Lime	4534
Lime	4570
Lime	4585

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1979
06-06-1979
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact
C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 7 day of June, 19 78, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: _____

[Signature]
Notary Public

Jo Ann Sarver

