

WELL PLUGGING RECORD

15-135-22003-00-00

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 1 TWP. 20S RGE. 26W E/W
Location as in quarters or footage from lines:

SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner KRM Petroleum Corp.

Lease Name BETZ Well No. 1-1

Office Address 817 17th Street, Denver, CO 80202

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed May 15, 1981

Application for plugging filed May 15, 1981

Plugging commenced May 15, 1981

Plugging completed May 15, 1981

Reason for abandonment of well or producing formation

No commercial quantity of oil or gas encountered.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Set 1st plug @ 960' with 65 sx.

Set 2nd plug @ 360' with 30 sx.

Set 3rd plug @ 40' with 10 sx.

Job complete 5:00 p.m., 5/15/81

RECEIVED
STATE CORPORATION COMMISSION
07-10-1981
JUL 10 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack L. Partridge, Vice President (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Cntr., Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 81

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My Commission expires: 2-4-85



CONTRACTOR'S WELL LOG

OPERATOR: KRM Petroleum Corp.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BETZ #1-1
 LOCATION: SE SW, Section 1-20S-26W
 Ness County, Kansas
 SPUD DATE: 5/06/81
 COMPLETION DATE: 5/15/81

0	2508	Sand & Shale
2508	2733	Shale & Redbed
2733	3105	Sand & Shale
3105	3291	Shale & Redbed
3291	3344	Sand & Shale
3344	3663	Shale & Lime
3663	3875	Shale & Sand
3875	4580	Shale & Lime
	4580	RTD

Spud @ 9:30 p.m. Cut 685' of a 12 1/4" hole in sand & shale. Ran 16 joints of 8 5/8" 20# casing set @ 680.61'. Cemented with 350 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 4:45 p.m., 5/06/81.

4580' RTD. Set 1st plug @ 960' with 65 sx. Set 2nd plug @ 360' with 30 sx. Set 3rd plug @ 40' with 10 sx., 5 sx. in rathole, 50-50 posmix, 6% gel. Plug was down @ 5:00 p.m., 5/15/81.

SAMPLE TOPS:

Anhydrite 1802'
 B/Anhydrite 1838'

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

RECEIVED
 STATE OF KANSAS
 07-10-1981
 CHIEF CLERK

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the BETZ #1-1, SE SW, Section 1-20S-26W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 8th day of July, 1981.

Suzanne M. Hofer
 Suzanne Hofer, Notary Public

