

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,802-0000

LEASE NAME Betz

WELL NUMBER 1

SPOT LOCATION NE NE SE

SEC. 1 TWP. 20 RGE. 26 ~~XX~~ or (W)

COUNTY Ness

Date Well Completed 5-3-85

Plugging Commenced 5-3-85

Plugging Completed 5-3-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Blue Goose Drilling Co., Inc.

ADDRESS P.O. Box 1413 Great Bend, KS 67530

PHONE # (316) 792-5633 OPERATORS LICENSE NO. 5104

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4530 T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	815'	8 5/8	812'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 4530 T.D.

150 Sacks 60-40 Posmix 2% Gel 3% cc
1st Plug @ 1770' W/50 sx Rathole 15 sx.
2nd Plug @ 840' W/50 sx Plug down 12:30 P.M. 5-3-85
3rd Plug @ 420' W/25 sx Steve Durrant State Plugger
4th Plug @ 40' W/10 sx Richard Lacy State Plugger on location.
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Blue Goose Drilling Co., Inc. License No. 5104
Address P.O. Box 1413 Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON

George E. Miller, Jr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George E Miller

(Address) Box 1413, Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 7th day of May, 1985

Helen C. Standley
Notary Public

My Commission expires: 12-8-87

