

15-007-10055-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 31 Twp. 31 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW
Lease Owner Aylward Drilling Co.
Lease Name Warren Mortgage #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 4/10/45 19____
Application for plugging filed 3/14/60 19____
Application for plugging approved 3/15/60 19____
Plugging commenced 3-30-60 19____
Plugging completed 4-5-60 19____
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production January 1960
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Elgin Depth to top 3348 Bottom 3420 Total Depth of Well 3472 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	160'	None
				7"	3472'	2490'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3472' and found it open.
Filled w/sand to 3450' and dumped 5 sacks of
cement with bailer. Pulled 7" casing.
Cleared hole and bailed hole to 260', set
rock bridge to 250' and dumped 20 sacks of
cement. Mudded the hole to 150', set rock
bridge to 140' and ran 10 sacks of cement.
Mudded the hole to 30', set rock bridge to
20' and ran 10 sacks of cement to base of
cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas
(If additional description is necessary, use BACK of this sheet)

AUG 10 1960
8-10-60
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1960

Thomas V. Sapp
Notary Public.

My commission expires 9-27-62

RP
WARREN MORTGAGE CO. #1

Casing Record: Company: Olson & Globe Location: C SW NW Sec. 31-31-11W
 Contractor: Patton Drilling Company Barber County, Kansas
 10 3/4" - 160' Commenced: March 12, 1945 Elevation: 1536
 7" - 3472' Completed: April 10, 1945

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Shale	0	110	Set 10 3/4" surface pipe @ 160' w/140 sacks cement.
Sand	110	140	
Red Shale	140	175	Geological Tops:
Red Shale & Shale	175	700	
Salt	700	800	Elgin Sand 3348
Shale & Red Shale	800	835	Lansing 3725
Shale & Shells	835	1545	Mississippian 4305
Lime	1545	1560	Viola 4578
Shale & Lime	1560	1600	DST 3343-60 Open 15" Gas in 3 min. BHP 1150#/5" - FP 300#
Lime	1600	1925	
Shale	1925	1965	DST 4298-4323 Open 30" Rec. 70' drilling mud, slight show of gas.
Shale & Shells	1965	1975	
Lime	1975	2010	Set 7" casing @ 3472' w/150 sacks cement.
Shale & Shells	2010	2040	
Lime	2040	2100	
Shale	2100	2175	
Shale & Lime	2175	2235	
Shale & Shells	2235	2435	
Lime & Shale	2435	2480	
Lime	2480	2540	
Shale	2540	2625	
Shale & Shells	2625	2840	
Lime	2840	3053	
Broken Lime	3053	3095	
Lime & Shale	3095	3115	
Lime	3115	3155	
Shale	3155	3325	
Shale & Lime	3325	3340	
Shale	3340	3341	
Lime	3341	3345	
Sand	3345	3425	
Shale & Shells	3425	3455	
Shale	3455	3495	
Lime	3495	3569	
Shale	3569	3652	
Shale & Broken Lime	3652	3772	
Lime	3772	4297	
Chat	4297	4395	
Shale	4395	4425	
Shale & Chat	4425	4452	
Lime	4452	4475	
Shale	4475	4566	
Lime	4566	4615 T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1960
 8-10-60
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 9th day of August, 1960

Paul W. Hesse
 Notary Public

My commission expires December 11, 1961