

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Basgall
 WELL NUMBER #2
990 Ft. from S Section Line
1650 Ft. from E Section Line
 SEC. 5 TWP. 16 RGE. 17 (E) or (W)
 COUNTY Rush
 Date Well Completed 10/2/65
 Plugging Commenced 3-11-96
 Plugging Completed 3-11-96
 by Duane Rankin (KCC District Agent's Name).

LEASE OPERATOR AFG Energy Inc.
 ADDRESS P.O. Box 458 Hays, Kansas 67601-0458
 PHONE#(913) 625-6374 OPERATORS LICENSE NO. 03456
 Character of Well Gas
 (Oil, Gas, O&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on 3-8-96 (date)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arb. & Top Depth to Top 2992' Bottom 3540' T.O. 3540'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|-------------|-------|-------|--------|--------|------------|
| Top | Gas / Water | 2992' | 2998' | 8 5/8" | 213 | None |
| Arb. | Gas / Water | 3533' | 3540' | 4 1/2" | 3533 | None |
| | | | | | | |
| | | | | | | |

RECEIVED
 KANSAS DEPT. OF REVENUE
 1996 MAR 11 AM 11:11 A

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet. Each set
Ran tubing to 3482'. Spotted 75 sxs. 60/40 Poz., 6% gel. Pulled up to 2440' and mixed 75 sxs. Pulled up to 1230' and filled hole. Took 55 sxs. Pulled tubing and filled hole with 15 sxs. Hooked to 8 5/8" and mixed 15 sxs. - Press. to 300#.

Name of Plugging Contractor Allied License No. _____
 Address Russell, Kansas 67665


03-16-1996

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.
 STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the same are true and correct, so help me God.

(Signature) Terry W. Piesker
 (Address) P.O. Box 458 Hays, Ks. 67601-0458

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 96



Linda K Peannenstiel
 Notary Public

USE SEPARATE COPIES OF EACH FORM

2/5/2000