


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rush County, Sec. 5 Twp. 16S Rge. 17 (A) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE
Lease Owner Frontier Oil Co.
Lease Name Basgall Well No. 1
Office Address 1720 Wichita Plaza
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 3-21 1963
Application for plugging filed _____ 19____
Application for plugging approved 7-12 19____
Plugging commenced 8-6 1973
Plugging completed 8-6 1973
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Archuleta Depth to top 2562 Bottom 3577 Total Depth of Well 3577 Feet
Show depth and thickness of all water, oil and gas formations. 2989

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Surface</u>	<u>0</u>	<u>210</u>	<u>8 3/4</u>	<u>210</u>	<u>0</u>
	<u>Casing</u>	<u>0</u>	<u>3576</u>	<u>4 1/2</u>	<u>3576</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 50 sz cement down annulus @ 500# press.
Mixed 20 sz cement & 20 sz gel and pumped down 4 1/2" casing
Pumped plug followed by 2 sz balls and 30 sz cement over press.
500# Standing press 500#

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1973
CONSERVATION DIVISION
Wichita, Kansas

08-08-1973

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allard Cementing Co., Inc.
Address Musell, Kans.


STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
1720 KSB&T Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of August 1973

Marguerite Mayfield
Notary Public.



15-165-19009-00-00

DRILLING LOG

Basgall No. 1

CASING RECORD:	COMPANY: Frontier Oil Company	DESCRIPTION:
8 5/8" @ 210'	CONTRACTOR: Red Tiger Drilling Co.	NE SW SE
w/135 sx cement	COMMENCED: February 15, 1963	S-165-17W
4 1/2" @ 3576 1/2'	COMPLETED: February 23, 1963	Rush County,
w/275 sx cement		Kansas
TOTAL DEPTH: 3577'		ELEVATION: 1988 DF 1991 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock Sod	0	70	
Blue Shale & Shells	70	211	
Shale & Sand Streaks	211	520	
Sand	520	780	
Red Bed	780	805	
Red Bed & Shale	805	1117	
Anhydrite	1117	1157	
Shale & Shells	1157	1895	
Shale & Lime	1895	3010	
Lime	3010	3180	
Lime & Shale	3180	3255	
Lime	3255	3525	
Lime & Chert	3525	3560	
Lime & Shale	3560	3577	

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1973
CONSERVATION DIVISION
Wichita, Kansas
07-12-1973

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 4th day of March, 1963.

Dorine V. Head
Notary Public

My Commission Expires:

11-17-68