

15165 20014-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80  
OCT 25 1982  
D-25-1982  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rush SEC. 2 TWP. 16S RGE. 17W E/W  
Location as in quarters or footage from lines:  
C SE SW SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Graham-Michaelis Corporation  
Lease Name Solomon Estate 1-2 Well No. \_\_\_\_\_  
Office Address P.O. Box 247 Wichita, Ks. 67201  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 10-6-82  
Plugging completed 10-14-82  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3529'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1098'	none
				4-1/2"	3524'	2537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3200' and ran 4 sacks cement. Shot casing @2991', 2794', 2623', 2534' and pulled a total of 79 joints of 4-1/2" casing. Plugged well with 3 sacks hulls, 10 sacks gel, 70 sacks cement, 1 sack hulls, 15 sacks gel, 8-5/8" plug, 100 sacks cement, 50/50 pos, 4% gel, 3% cc.  
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1982

My Commission expires:



Irene Hoover  
Notary Public.

15-165-20614-00-00

DRILLERS LOG

No. 1-2 Solomon Estate

CASING RECORD:	COMPANY:	Graham-Michaelis Corporation	DESCRIPTION:
3 5/8" @ 1,098' w/500 sx cement	CONTRACTOR:	Red Tiger Drilling Company	C SE/4 SW/4 SE/4 Sec. 2-T16S-R17W Rush County, Kansas
4 1/2" @ 3,524' w/125 sx cement	COMMENCED:	July 9, 1977	
	COMPLETED:	July 21, 1977	
TOTAL DEPTH: 3,529'			ELEVATION: 1,936' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Post Rock & Clay	0	110	
Shale	110	232	
Sand	232	354	
Shale	354	467	
Sand	467	703	
Red Bed	703	1077	
Anhydrite	1077	1114	
Shale	1114	1750	
Lime & Shale	1750	2838	
Lime	2838	3529	
RTD		3529	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 26th day of July, 1977.

Joyce A. Hagermann  
Notary Public

Rec'd  
10-25-1982

