

LEASE NAME Urban

WELL NUMBER 1

SPOT LOCATION 990 FSL
4950 FEL

SEC. 2 TWP. 16RGE. 17 or (W)

COUNTY Rush

Date Well Completed 3/18/82

Plugging Commenced 12/29/86

Plugging Completed 12/29/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bennett & Schulte Oil Company

ADDRESS Box 329, Russell, Kansas 67665

PHONE # 913 483-2721 OPERATORS LICENSE NO. 6246

Character of Well Oil - no longer commercial.
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District # 1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation C. Sand Depth to top 3505 bottom 3510 T.D. 3595

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
			987	8 5/8"	987	None
		0	3594	4 1/2"	3594	1901'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged back to 3429' with 165' sand and 4 sacks cement - pulled pipe from 1901'. Mixed 25 sacks hulls, 15 sacks Gel, 50 sacks cement, 10 sacks Gel, 1 sack hulls - Release plug, 150 sacks cement. Maximum pressure 800#, Shut In 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bennett & Schulte Oil Company License No. 325
Address Box 329, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Russell, ss.

Reginald Bennett (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Reginald Bennett

(Address) Box 329, Russell, Kas. 67665

SUBSCRIBED AND SWORN TO before me this day of , 19

Ralph L. Schulte
Notary Public

My Commission expires: 5-21-89



STATE CORPORATION COMMISSION
Form 100-A-12-1987
Revised 06-85
CONSERVATION DIVISION
Wichita, Kansas