


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-165-20015-00-00 Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 7 Twp. 16 Rge. 17 (E) (W)
Location as "NE/CNW*SW*" or footage from lines SW SW NE
Lease Owner Frontier Oil Company
Lease Name Breit Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 1/15/68 19____
Plugging completed 1/17/68 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3508 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1104'	none
				4-1/2"	3494'	2480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3000', dumped 4 sacks of cement.
Shot pipe at 2765', 2672', 2574', 2478', worked pipe loose and pulled 75 joints. Set 10' rock bridge at 420', dumped 6 yards ready mix and tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1968
CONSERVATION DIVISION
Wichita, Kansas

01-22-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1968

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

15-165-20015-00-00

DRILLERS LOG

Breit No. 2

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 1104'	CONTRACTOR:	Red Tiger Drilling Co.	SW SW NE
w/425 sx cement	COMMENCED:	March 15, 1967	7-16S-17W
4 1/2" @ 3494'	COMPLETED:	March 24, 1967	Rush Co., Ks.
w/150 sx cement			ELEVATION: 1957 DF
			1960 RB
TOTAL DEPTH: 3508'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	460	
Sand & Shale	460	620	
Sand	620	695	
Shale	695	1086	
Anhydrite	1086	1126	
Shale	1126	1795	
Shale & Lime	1795	2965	
Lime	2965	3508	

DEC 24 1967
 12-21-1967
 RECORDS DIVISION
 WICHITA, KANSAS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 28th day of March, 1967.

Jean Shelton
 Notary Public

My Commission Expires:

5-22-70

dup

15-165-20015-00 **COPY**

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY FRONTIER OIL


SEC. 7 T. 16 N. 17W
LOC. SW SW NE

FARM Breit NO. 2

COUNTY Rush

TOTAL DEPTH 3508
CDMM. 3-15-67
SHOT OR TREATED
CONTRACTOR RED TIGER DRLG.
ISSUED 5-20-67

COMP. 3-24-67



CASING
20 10
15 8 5/8" @ 1104' w/425SX
12 6
13 4 1/2" @ 3494' w/150 SX

ELEVATION 1960' KB

PRODUCTION 1089 MCFGPD/TOP-LAN
ARB 3133-3510

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATION	FROM	TO	REMARKS
Shale	0	460	
Sand & Shale	460	620	
Sand	620	695	
Shale	695	1086	
Anhydrite	1086	1126	
Shale	1126	1795	
Shale & Lime	1795	2965	
Lime	2965	3508	

RECEIVED
STATE CORPORATION COMMISSION
JAN - 8 1968
CONSERVATION DIVISION
Wichita, Kansas

01-08-1968

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 28th day of March, 1967.

John A. Bellan
Notary Public

My Commission Expires:
5-22-70

Elevation	1957 DF	1960 RB
Anhydrite	1086	(+874)
Topeka	2957	(-997)
Heebner	3187	(-1227)
Lansing-Kansas City	3239	(-1279)
Base of Kansas City	3447	(-1487)
Arbuckle	3492	(-1532)
Rotary Total Depth	3508	(-1548)
4 1/2" Pipe At	3494	(-1534)