

15-105-20009-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rush County, Sec. 7 Twp. 16S Rge. 17W (E) (W)

Location as "NE/CNWKSWK" or footage from lines C S $\frac{1}{2}$ S $\frac{1}{2}$ SE

Lease Owner Frontier Oil Company

Lease Name Hartman Well No. 2

Office Address 1720 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed February 28 1967

Application for plugging filed February 28 1967

Application for plugging approved February 28 1967

Plugging commenced February 28 1967

Plugging completed February 28 1967

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Depth to top Bottom Total Depth of Well 3533 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1100'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud
500'. Set plug w/1/2 sx
hulls & 25 sx cement.
Filled hole w/heavy mud
40'. Set plug w/1/2 sx
hulls & 8 sx cement.

RECEIVED
MAR 10 1967
03-10-1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Starr (employee of owner) or Notary Public

I, Maxine V. Starr, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr

1720 Wichita Plaza - Wichita, Ks.
(Address)

Subscribed and sworn to before me this 9th day of March, 1967

Jean Hollan
Notary Public

My commission expires 5-22-70

15-165-20009-00-00

DRILLERS LOG

Hartman No. 2

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 1100'	CONTRACTOR:	Red Tiger Drilling Co.	C S $\frac{1}{2}$ S $\frac{1}{2}$ SE
w/450 sx cement	COMMENCED:	February 17, 1967	7-16S-17W
	COMPLETED:	February 28, 1967	Rush Co., Ks.
			ELEVATION: 1966 DF
			1969 RB

TOTAL DEPTH: 3533'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Cellar Clay	0	18	
Post Rock	18	45	
Shale & Shells	45	355	
Shale	355	520	
Sand	520	740	
Shale, Shells & Red Bed	740	760	
Red Bed & Shale	760	1088	
Anhydrite	1088	1128	
Shale & Red Bed	1128	1430	
Shale & Shells	1430	1830	
Shale & Lime	1830	2965	
Lime	2965	3138	
Lime & Shale	3138	3175	
Lime	3175	3533	

RECEIVED
 STATE GEOLOGICAL COMMISSION
 MAR 10 1967
 03-10-1967
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 9th day of March, 1967.

Jean Hollan
 Notary Public

My Commission Expires:

5-22-70