


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 11 Twp. 16 Rge. (E) 17 (W)
Location as "NE/CNWxSWx" or footage from lines NW NW NW
Lease Owner Iron Drilling Company
Lease Name Stegman Well No. 1
Office Address 1206 Philtower Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 13 19 56
Application for plugging filed December 13 19 56
Application for plugging approved December 13 19 56
Plugging commenced December 13 19 56
Plugging completed December 13 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brandage
Producing formation None Depth to top Bottom Total Depth of Well 3594 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topoka		3009		8-5/8	1128	None
Toronto		3254				
Lansing		3286				
Conglomerate		3531				
Arbuckle		3544				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 260 feet. Set cement plug using 20 sacks of cement and 1/2 sack of hulls. Filled hole with heavy mud to 40 feet. Set cement plug using 10 sacks of cement and 1/2 sack of hulls. Cement filled to drilling nipple.

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1956
CONSERVATION DIVISION
Wichita, Kansas

12-29-1956

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Iron Drilling Company
Address 1206 Philtower Bldg., Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (conservation operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole
Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1956

B. Michal

My commission expires Feb. 28, 1960

Notary Public.

PLUGGING
FILE SEC. 11 T. 16 R. 17W
BOOK PAGE 126 LINE 24

15-1165-00089-00-00

DRILLING RECORD

Well: Stegman No. 1
NW NW NW Sec. 11-16S-17W
Rush County, Kansas

1128' 8-5/8" Surface Casing
cemented w/500 sacks.

Work Commenced: 12- 1-56
Drilling Commenced: 12- 1-56
Drilling Completed: 12-13-56
Work Completed: 12-14-56

WELL LOG

Surface clay	0	to	20
Rock	20	to	135
Shale	135	to	220
Shale, sand & shells	220	to	610
Shale & shells	610	to	640
Sand	640	to	767
Shale, red bed	767	to	960
Red bed	960	to	1118
Anhydrite	1118	to	1157
Red bed	1157	to	1225
Shale & shells	1225	to	1350
Shale	1350	to	1600
Shale, shells & salt	1600	to	1840
Shale & lime streaks	1840	to	1850
Lime & shale	1850	to	2195
Sandy lime & pyrite iron	2195	to	2240
Sandy lime & shale	2240	to	2300
Lime & shale	2300	to	2330
Shale & lime streaks	2330	to	2410
Lime & shale	2410	to	2540
Lime	2540	to	2595
Lime & shale	2595	to	3085
Lime	3085	to	3563
Arbuckle	3563	to	3594 T. D.

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1956

CONSERVATION DIVISION
Wichita, Kansas

12-29-1956

PLUGGING			
FILE	SEC. 11	T. 16	R. 17W
BOOK	PAGE 126	LINE	24