


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-165-00156-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 11 Twp. 16 Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Davis Brothers

Lease Name Breit Well No. 1

Office Address 11 East Third, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 21 19 55

Application for plugging filed December 21 19 55

Application for plugging approved December 21 19 55

Plugging commenced December 21 19 55

Plugging completed December 21 19 55

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation Depth to top Bottom Total Depth of Well 3595 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1103'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud to top. Squeezed with 500# pressure from top with 100 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 1005 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.

L. J. Clampitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. J. Clampitt*
1005 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 55

Dorlene May
Notary Public.

My commission expires September 30, 1959

PLUGGING
FILE SEC 11 T 16 R 17W
BOOK PAGE 26 LINE 32

12-30-1955

15-165-00156-00-00

ROTARY DRILLING LOG

OPERATOR: Davis Brothers
Breit #1
SE SE SE Sec. 11-16-17W,
Rush County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 12/7/55
COMP: 12/21/55

Formations:

Remarks: Set 8-5/8" surface casing at
1103' with 500 sacks pozmix, 2% c. c.

Lime & Shale & Stone	80'
Shale & Shells	255'
Shale & Clay	485'
Shale	592'
Sand & Shale	615'
Shale & Shells	822'
Red Bed	1045'
Red Bed & Shells	1093'
Anhydrite	1132'
Shale & Shells	1460'
Shale Salt & Shells	1805'
Shale & Shells	1980'
Lime & Shale	2100'
Lime	2289'
Lime & Shale	3060'
Lime	3495'
Lime & Shale	3547'
Conglomerate	3563'
Lime	3595'
Rotary Total Depth (D&A)	3595'

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

PLUGGING
FILE SEC 11 T 16 R 17W
BOOK PAGE 26 LINE 27

12-30-1955