

15-165-20452-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County, Sec. 11 Twp. 16S Rge. 17 (~~E~~ W) (W)  
Location as "NE/CNW/SE" or footage from lines 1485' FEL & 990' FNL (C E/2 SE NW NE  
Lease Owner Clinton Oil Company  
Lease Name Stegman Well No. 2-D  
Office Address 217 North Water, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed December 9, 1972  
Application for plugging filed December 9, 1972  
Application for plugging approved December 9, 1972  
Plugging commenced December 10, 1972  
Plugging completed December 10, 1972  
Reason for abandonment of well or producing formation No Productible Zone



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3542 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1069	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud, pushed 1/2 sack hulls and plug to 360 feet. Cemented with 25 sacks cement through drill pipe. Filled hole with heavy mud, pushed 1/2 sack hulls and plug to 40 feet. Cemented with 10 sacks cement to base of well cellar. Job complete at 7:00 AM 12-10-72.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
12-26-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.  
Ben E. Unruh (employee of owner) ~~is~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh  
Box 1164, Great Bend, Kansas 67530  
(Address)


SUBSCRIBED AND SWORN TO before me this 19th day of December 19 72

My commission expires July 8, 1974

Notary Public.

COMPANY **Clinton Oil Company**  
 FARM **Anna Stegman** NO. **2-D**  
 TOTAL DEPTH **3542'**  
 COMM. **11-30-72** COMP. **12-10-72**  
 CONTRACTOR **Garvey Drilling Company**

SEC. **11** T. **16S** R. **17W**  
 LOC. **C E/2 SE NW NE**  
 COUNTY **Rush, Kansas**



CASING  
**8 5/8" @ 1069' w/450ex**

ELEVATION  
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 60' Post Rock
- 70' Shale
- 290' Sand
- 420' Shale
- 687' Sand
- 883' Shale
- 1059' Shale & Red Bed
- 1069' Anhydrite
- 1340' Shale
- 2120' Lime & Shale
- 2915' Shale & Lime
- 3000' Lime & Shale
- 3262' Lime
- 3340' Lime & Shale
- 3350' Lime
- 3542' Lime
- 3542' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 26 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-26-1972

State of Kansas }  
 County of Barton } SS

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Anna Stegman #2-D well.

Charlene Marker

Subscribed and sworn to before me this 19th day of December 19 72

My Commission Expires: July 8, 1974

James H. McQueen  
 NOTARY PUBLIC