

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20,733-00 00

LEASE NAME Burgardt A #8

WELL NUMBER _____

SPOT LOCATION 50' N of NE NE NE

SEC. 15 TWP. 16S RGE. 17W (E) or (W) (W)

COUNTY Rush

Date Well Completed _____

Plugging Commenced 10/2/84

Plugging Completed 10/31/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3667'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	274'	none
				4 1/2"	3578'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Sanded bottom to 3120' & 4 sacks cement. Shot pipe at 1075'. Pumped 3 sacks cement down annulus, pressured to 400#. Pumped 97 sacks cement down 4 1/2" @ 950#. Shut in @ 750# (cement - 60/40 poz 2% gel.)

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1984



My Commission expires: _____

Irene Hoover
Notary Public

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 165 — 20,733 — ~~10-00~~
County Number

S. 15 T. 16S R. 17W E
Loc. 50' N of NE/4 NE/4 NE/4
County Rush

Operator
Frontier Oil Company

Address
1720 KSB&T Building, Wichita, Kansas 67202


Well No. 8 Lease Name Burgardt "A" (Twin)

Footage Location 280 FNL 330 FEL
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Red Tiger Drilling Company Geologist Richard Parker

Spud Date 9/10/79 Date Completed 9/22/79 Total Depth 3,667' P.B.T.D. 3220

Directional Deviation Oil and/or Gas Purchaser Kansas-Nebraska Nat. Gas



Elev.: Gr. _____
DF _____ KB 1,999'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	28#	274'	Common	160	2% Gel, 3% C.C.
Production	7 7/8"	4 1/2"	10.5#	3,578'	Common	825	10% Salt, 4% Gel & 6% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					3170-76

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 11-15-79 Producing method (flowing, pumping, gas lift, etc.) Flow

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	0 bbls.	52 MCF	0 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Sold Producing interval(s) 3170-76

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1984
08-31-1984
CONSERVATION DIVISION
Wichita, Kansas