

15-165-20270-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rush SEC. 15 TWP. 16S RGE. 17W E/W
 Location as in quarters or footage from lines:

SE NE NE

Lease Owner Southern States Oil Company

Lease Name Burgardt A-4 Well No. _____

Office Address P.O. Box 1365 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 7-21-83

Plugging completed 7-27-83

Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey

Producing formation _____ Depth to top _____ bottom T.D. 3605'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1142'	none
				4-1/2"	3604'	2078'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged off bottom with sand to 2650' and ran 5 sacks cement. Shot casing @2600',
2542', 2438', 2336', 2210', 2113' and layed down a total of 62 joints of 4 1/2" casing.
Plugged well with 3 hulls, 10 gel, 70 cement, 15 gel, 1 hull and 175 sacks 50/50 pos,
4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 83

My Commission expires:



Irene Hoover
 Notary Public.

STATE OF KANSAS
 RECEIVED
08-01-1983
 AUG 01 1983

15-165-20270-00-00

DRILLERS LOG

No. 4 Burgardt "A" ✓

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 1142' w/450 sx cement	CONTRACTOR:	Red Tiger Drilling Company	SE NE NE 15-16S-17W
4 1/2" @ 3604' w/250 sx cement	COMMENCED:	October 28, 1969	Rush County, Kansas
TOTAL DEPTH: 3605'	COMPLETED:	November 7, 1969	ELEVATION: 2036 DF 2039 RB


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand, Shale	0	490	
Shale	490	530	
Sand	530	778	
Shale	778	1132	
Anhydrite	1132	1175	
Shale	1175	1980	
Shale & Lime	1980	2140	
Lime	2140	2275	
Lime & Shale	2275	3030	
Lime	3030	3520	
Lime & Conglomerate	3520	3560	
Lime	3560	3605	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 13th day of November, 1969.



Gloria Fawcett
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 07 1983

CONSERVATION DIVISION
Wichita, Kansas

07-07-1983