

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20,249

LEASE NAME Burgardt A #2

WELL NUMBER _____

SPOT LOCATION NW NE NE

SEC. 15 TWP. 16s RGE. 17w (E) or (W)

COUNTY Rush

Date Well Completed _____

Plugging Commenced 10/3/84

Plugging Completed 10/31/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3579'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1156'	none
				4 1/2"	3563'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 30 sacks cement, released plug to 3000'. Shot pipe at 2440' & 2330'. Pipe parted Got 1 joint. Plugged well with 250 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1984



My Commission expires:

Notary Public

15-165-20249-00-00

DRILLERS LOG

No. 2 Burgardt "A"

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 1156'	CONTRACTOR:	Red Tiger Drilling Co.	NW NE NE
w/425 sx cement	COMMENCED:	July 31, 1969	15-16S-17W
4 1/2" @ 3563'	COMPLETED:	August 8, 1969	Rush County,
w/250 sx cement			Kansas
TOTAL DEPTH: 3579'			ELEVATION: 1998 GL
			2001 RB


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	535	
Sand	535	790	
Shale	790	1137	
Anhydrite	1137	1178	
Shale	1178	1835	
Line & Shale	1835	2140	
Line	2140	2275	
Line & Shale	2275	2955	
Line	2955	3520	
Line & Shale	3520	3575	
Line	3575	3579	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 22nd day of August, 1969.



Gloria Fawcett
Notary Public

My Commission Expires:
10-25-72

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1969

CONSERVATION DIVISION
Wichita, Kansas

08-31-1984