

LEASE NAME Clark

WELL NUMBER #3

660 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 19S RGE. 30W (E) or (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 11/30/98

Plugging Completed 11/30/98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE ( 785 ) 785-798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing Formation Marmington Depth to Top 4605 Bottom 4611 T.D. 4655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmington				8 5/8	342	
				4 1/2	4655	761' pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set Sanded the bottom off & spotted 4 sks of cement with a dump bailer. Perforated 4 1/2 @ 1300'. Mixed 50 sks + 50# hulls in the last 20 sks & pumped down. Shot the casing off @ 761', pulled to 650' & pumped a 50 sk plug. Pulled to 350' & pumped a 40 sk plug. Pulled pipe out and topped off with 15 sks.

Name of Plugging Contractor Allied Cementing Co Inc License No. \_\_\_\_\_

Address P O Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc.

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 98

Debra Kerr  
Notary Public Debra Kerr

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM