

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TOO OLD
DRLD 2-5-60

15-051-01704-0001

API NUMBER

LEASE NAME MEIER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

1650 Ft. from S Section Line

2970 ~~2630~~ Ft. from E Section Line

SEC. 17 TWP. 14 RGE. 19 X5000(W)

COUNTY ELLIS

Date Well Completed

Plugging Commenced 12-27-89

Plugging Completed 12-27-89

LEASE OPERATOR R P NIXON OPERATIONS INC

ADDRESS 207 W 12TH, HAYS KS 67601

PHONE# (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-27-89 (date)

by MARION SCHMIDT, HAYS OFFICE (KCC District Agent's Name).

Is ACO-1 filed? TOO OLD If not, Is well log attached? FILED WITH CP-1

Producing Formation ARBUCKLE Depth to Top 3818' Bottom T.D. 3822'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
SURFACE		SURF	200	8 5/8	200	NONE
PRODUCTION		SURF	3818	5 1/2"	3818	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TUBING AT 3800', cemented with 100 sx 65/35 POZMIX 6% GEL W/100lbs hulls, pulled tubing to 2300', cemented with approx 245 sx 65/35 POZMIX 6% GEL W/250lbs hulls. Cement did circulate to surface. Pulled tubing out of hole, cemented with 30 sx 65/35 POZMIX, 6% GEL, MAX PRESS 550 PSI, SHUT IN ANNULUS 300 PSI NO CEMENT (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION License No. 5128

Address 207 W 12TH, HAYS KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R P NIXON OPERATIONS INC

STATE OF KANSAS COUNTY OF ELLIS, ss.


DAN A NIXON

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Dan Nixon*

(Address) 207 W 12TH, HAYS KS 67601



AND SWORN TO before me this 8TH day of JANUARY, 19 90

Lorna M. Herrman
Notary Public

My Commission Expires: 6-19-92

Lorna M Herrman

15-051-01704-00-01

DRILLERS LOG No. 2 Seitz

CASING RECORD: COMPANY: Frontier Oil Company DESCRIPTION: SE NE SW
 8 5/8" @ 202' CONTRACTOR: Red Tiger Drilling Co. 17-14E-19W
 w/138 cement Ells County
 5 1/2" @ 3813' COMPLETED: December 8, 1959 ELEVATION: 2190 DF
 w/138 cement COMPLETED: December 18, 1959 2193 RB
 TOTAL DEPTH: 3822 (-1629)

FORMATION	FROM	TO	REMARKS
Soil and Clay	0	40	
Shale Shells	40	202	
Shale & Shells	202	400	
Red Shale & Shells	400	600	
Shale & Sand	600	770	
Shale & Shells	770	860	
Sand & Shells	860	1115	
Red Bed & Shells	1115	1438	
Shale Shells	1438	1463	
Anhydrite	1463	1507	
Shale Shells	1507	1860	
Shale & Shells	1860	2035	
Lime & Shale	2035	2415	
Lime	2415	2685	
Lime & Shale	2685	2960	
Shale Lime	2960	3185	
Lime & Shale	3185	3385	
Lime	3385	3683	
Lime	3683	3770	
Lime & Shale	3770	3810	
Conglomerate	3810	3813	
Arbuckle	3813	3822	

RECEIVED
 STATE CORPORATION COMMISSION

OCT 19 1965

CONSERVATION DIVISION