


WELL PLUGGING RECORD

All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 17 Twp. 14S Rge. 19W(E) (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Frontier Oil Company
Lease Name Seitz Well No. 2
Office Address 1720 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed December 3 19 65
Application for plugging approved December 3 19 65
Plugging commenced December 3 19 65
Plugging completed December 3 19 65
Reason for abandonment of well or producing formation Non commercial

If a producing well is abandoned, date of last production September 30 19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Kansas City Depth to top 3542 Bottom 3547 Total Depth of Well 3832 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200'	8 5/8"	200'	None
		0	3818'	5 1/2"	3818	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pressured up 8 5/8" and it did not hold.
Pumped 20 sacks of cement and it had a closed
in pressure of 150#. Pumped 35 sacks of gel
mud down casing. Pumped plug down casing with
50 sacks of cement. Plug at 400'. Maximum
pressure 400#. Closed in pressure 250#.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton
Address P.O. Box 339, Hays, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Starr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1965

My commission expires 5-22-66 Notary Public.

15-051-01704-0000

DRILLERS LOG No. 2 Seitz

CASING RECORD: 8 5/8" @ 202' w/125 ex cement
 5 1/2" @ 3813' w/125 ex cement
TOTAL DEPTH: 3822 (-1029)

COMPANY: Frontier Oil Company
CONTRACTOR: Red Tiger Drilling Co.
COMMENCED: December 8, 1959
COMPLETED: December 18, 1959

DESCRIPTION: SE NE SW 17-14N-19W Ellis County Kansas
ELEVATION: 2100 DF 2153 NS

FORMATION	FROM	TO	REMARKS
Soil and Clay	0	40	
Shale Shells	40	202	
Shale & Shells	202	400	
Red Shale & Shells	400	500	
Shale & Sand	500	770	
Shale & Shells	770	800	
Sand & Shells	800	1115	
Red Bed & Shells	1115	1435	
Shale Shells	1435	1493	
Anhydrite	1493	1807	
Shale Shells	1807	1860	
Shale & Shells	1860	2038	
Lime & Shale	2038	2415	
Lime	2415	2585	
Lime & Shale	2585	2800	
Shale Lime	2800	3188	
Lime & Shale	3188	3288	
Lime	3288	3683	
Lime	3683	3770	
Lime & Shale	3770	3810	
Conglomerate	3810	3813	
Arbuckle	3813	3822	

RECEIVED
 STATE CORPORATION COMMISSION

OCT 19 1965

CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 22nd day of December, 1959.

Dennis Head
 Notary Public

My Commission Expires:

11-17-62