

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 - 101 - 21,297

LEASE NAME McMillen

WELL NUMBER 1

SPOT LOCATION NW SE SW

SEC. 1 TWP. 20 RGE. 29 (X) or (W)

COUNTY Lane

Date Well Completed 3-15-86

Plugging Commenced 3-15-86

Plugging Completed 3-15-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MIDCO EXPLORATIONS, INC.
ADDRESS 200 East 1st St. Suite 411, Wichita, KS 67202

PHONE # (316) 267-3613 OPERATORS LICENSE NO. 5254

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation D&A Depth to top _____ bottom T.D. 4690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	332'	8 5/8	330'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

4690' T.D. 195 sx 60-40 Posmix 6% Gel Solid Bridge @ 40' w/10 sx
1st Plug @ 2172' w/50 sx Bathole 15 sx
2nd Plug @ 1386' w/80 sx Plug down 2:15 P.M. 3-15-86
3rd Plug @ 360' w/40 sx

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor BLUE GOOSE DRILLING COMPANY, INC. License No. 5104
Address P.O. Box 1413 Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

MARTIN E. MILLER (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Mart E Miller

(Address) Box 1413, Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 17 day of March, 19 86

Helen C Standley
Notary Public

My Commission expires: 12-8-87

MAR 21 1986
3-21-86
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 3 5 1986 month day year

API Number 15- 101-21,297-0000

OPERATOR: License # 5254 Name Midco Exploration, Inc. Address 200 E. 1st. St. - Suite 411 City/State/Zip Wichita, Ks. 67202 Contact Person Harvey Gough Phone 316-267-3613

NW SE SW Sec. 1 Twp. 20 S. Rg. 29 East West 990 3630 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5104 Name Blue Goose Drilling Co., Inc. City/State Great Bend, Ks.

Nearest lease or unit boundary line 990 feet County Lane

Lease Name McMillen Well # 1

Ground surface elevation 2814 feet MSL

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Surface pipe by Alternate: 1 2 X

Depth to bottom of fresh water 180

Depth to bottom of usable water 1100

Surface pipe planned to be set 300

Projected Total Depth 4600 feet

Formation MISSISSIPPI

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 2/28/86 Signature of Operator or Agent Harvey Gough Title Vice President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt 1 2

This Authorization Expires 3-28-86 Approved By 3-28-86

3-7-86 Mon

300 2 1/2

No

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and size of plug (e.g., 60-40 poz. mix). Includes entries for 1st through 5th plugs and a mousehole.

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

Handwritten notes and signatures: PUSHER Martin Miller, TD 4690 FORMATION MISSISSIPPI, SURFACE PIPE 8 5/8 @ 370, ANHYDRITE 2147-72 ELEVATION 2814, COMPLETION TIME & DATE 2:50 p.m. 3/15/86, 1st PLUG @ 2172 FT. W/ 50 SX, 2nd PLUG @ 1386 FT. W/ 80 SX, 3rd PLUG @ 360 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 18, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/, CEMENT COMPANY Allied, TECHNICIAN, Base Ann 50 SX, 1/2 Ann + 300 80 SX, SP + 30 - 40 SX, SB at 40' - 10 SX, RA 40% 15 SA

MAR 20 1986

CONSERVATION DIVISION Wichita, Kansas