

API NUMBER 15-101-21,691-0000

LEASE NAME Smid

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 30 TWP. 20S RGE. 28 (X) or (Y)

COUNTY Lane

Date Well Completed 01-01-95

Plugging Commenced 12-31-94

Plugging Completed 01-01-95

LEASE OPERATOR Rheem Resources, Inc.

ADDRESS 100 S. Main, Suite 505, Wichita, Ks. 67202

PHONE# (316) 262-5099 OPERATORS LICENSE NO. 31283

Character of Well D&A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-29-94 (date)

BY Steve Middleton, Dodge City (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, - from feet to feet each set
Fill w/heavy mud: 1st plug from 2130' - 1930' with 50 sks, 2nd plug from 1180' - 860' with 80 sks, 3rd plug from 600' - 440' with 40 sks, 4th plug from 280' - 80' with 50 sks, 5th plug from 40' - 0' with 10 sks, 15 sks rat-hole, total 245 sks 80% cement, 20% posmix, 6% gel with 1/2# floeal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, Ks. 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rheem Resources, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Jack K. Wharton


(Address) 150N. Main, Ste 801, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 7 day of Feb, 19 95

Sandra C. McCaig
 Notary Public

My Commission Expires: 1-31-98

USE ONLY ONE SIDE OF EACH FORM



EFFECTIVE DATE: 11-27-94

State of Kansas

101-21,691-6000

FORM MUST BE TYPED

DISTRICT # 4

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date December 5 1994
month day year

Spot NE SW SW Sec 30 Twp 20 S, Rg 28 X East West

OPERATOR: License # 31283
Name: Rheem Resources, Inc.
Address: Suite 505 100 South Main
City/State/Zip: Wichita, KS 67202
Contact Person: Clay Hedrick, Jr.
Phone: 316-262-5099

990 feet from South / North line of Section
990 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: Smid Well #: 1
Field Name: _____

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other _____

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Lansing-Kansas City
Nearest lease or unit boundary: 990 feet
Ground Surface Elevation: Approx. 2750 feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1180'
Surface Pipe by Alternate: ... 1 X 2
Length of Surface Pipe Planned to be set: 250 - 300'
Length of Conductor pipe required: _____
Projected Total Depth: 4600 feet
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well ... farm pond ... X other

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____
Exp. 5/22/95

Will Cores Be Taken?: ... yes X no
If yes, proposed zone: _____

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Tony
SPUD DATE 12/20-94 INIT. SD
LENGTH SURFACE PLANNED 250+
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 256 CONDUCTOR
ANHYDRITE T- B-2126 ELEVATION
TD 4751 FORMATION Miss
RAN PIPE @ SX DV TOOL ALT II DONE
@ SX Y N
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX
Anhydrite Base @ 2130 Ft. W/ 50 SX
1/2 Base Anyh. @ 1180 Ft. W/ 80 SX
1/2, 1/2 Plug @ 600 Ft. W/ 40 SX
Bottom Surface @ 280 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
WATER WELL _____ SX (Irr. Well Pond Hauling)
TECHNICIAN Sam DATE 12-29-94
TYPE OF CEMENT IAN @ 6/40 676 1/4 Fbs
STARTING TIME 12:20 (AM/PM) DATE 1-1-95
COMPLETION TIME 5:45 (AM/PM) DATE 1-1-95
CEMENT COMPANY F/br/d