

#1

LEASE NAME Janson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 29TWP. 16RGE. 17 (N) or (W)

COUNTY Rush

LEASE OPERATOR AFG Energy Inc.

ADDRESS Box 458 Hays, Ks. 56501-0458

PHONE#(913) 625-6374 OPERATORS LICENSE NO. 03456

Date Well Completed 6-26-65

Plugging Commenced 3-31-94

Character of Well Gas

Plugging Completed 4-19-94

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-28-94 (date)

by Duane Rankin (XCC District Agent's Name).

Is ACC-1 filed? Yes If not, is well log attached?

Producing Formation LKC & Topeka, Tarkio Depth to Top 2744' Bottom 3581' T.O. 3581'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled out
Tarkio	Gas	2744'	2750'	8 5/8"	212	-
Topeka	Gas & Water	2954'	3212'	4 1/2"	3575	-
L-KC	Gas & Water	3326'	3581'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from feet to feet each set.
3-31-94 Mixed 30 sx. 65/35 Poz., 8% gel down 8 5/8" & pressured to 500#. Mixed 195 sx. 65/35 Poz., 8% gel & 500# Hulls down 4 1/2" Casing. Max Press - 800# SIP - 100#. Check TD - 280'.
4-19-94 Mixed 20 sx. 60/40 Poz. and loaded hole

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Ks.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1994
04-22-1994
CONSERVATION DIVISION
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Plesker (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed on the same are true and correct, so help me God.

(Signature) Terry W. Plesker

(Address) 1327 Noose Rd, P.O. Box 458 Hays, Ks.



AND SWORN TO before me this 21st day of April, 19 94

Linda K. Pfannenstiel
Notary Public

My Commission Expires: 2/5/96