

15-007-01561-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 34 Twp. 31S Rge. 11 (E) W. (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE SW

Lease Owner Great Lakes Carbon Corporation

Lease Name Hugh Davenport Well No. 1

Office Address 501 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-9- 19 44

Application for plugging filed 2-9- 19 44

Application for plugging approved 2-9- 19 44

Plugging commenced 2-9- 19 44

Plugging completed 2-10 19 44

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Depth to top Bottom Total Depth of Well 4445 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
None	None			10-3/4	354	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated heavy mud from total depth 4445 every 700 feet to 354

Cement 15 sacks 354 to 324

Mud from 324 to 26

Cement 10 sacks 26 to 6

PLUGGING
FILE SEC 34-31R11W
BOOK PAGE 127 LINE 44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Lakes Carbon Corporation
Address 501 Petroleum Building, Wichita, 2, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

W. J. Cofferidge (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Cofferidge

(Address) 501 Petroleum Building, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of February 19 44

My commission expires Nov. 8, 1947

Notary Public



GREAT LAKES CARBON CORPORATION
No. 1 Davenport

Sec. 34 Twp. 31S, Rge. 11W
SE SE SW Barber Co., Kans.

Commencement date: 1-11-44
Completion date: 2-7-44

Initial Potential: Dry

Casing record: 10-3/4" OD -- 354'

Red bed and shells	880
Shale and shells	1365
Lime	1385
Shale, Shells, and salt	1565
Lime and shale	1708
Lime	1965
Lime and shale	2070
Lime	2144
Lime and shale	2820
Shale	2895
Lime	3326
Shale	3403
Broken lime and shale	3480
Lime and shale	3684
Shale	3736
Lime	3892
Lime and shale	3920
Lime	4284
Lime and shale	4409
Lime and chat	4437
Lime	4445 T.D.

GEOLOGICAL DATA

Top Lansing	3775
Fine sand	4384-95 S.S. oil
Top Mississippian	4395
T. D.	4445


I hereby certify that this is a true and correct copy of the log as kept by the driller on the above well.

Harold E. McNeil

Subscribed and sworn to before me this 14th day of February,
A.D., 1944.

Helen Blood Oakes
Notary Public

My commission expires: November 8, 1947



2-15-44