

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas. 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 16 TWP. 31s RGE. 11w E/W
Location as in quarters or footage from lines:
100' SW of C SE NE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Lario Oil & Gas Co.
Lease Name Watkins-Smith Unit #1 Well No. _____
Office Address 301 S. Market St., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11/30/83
Plugging completed 12/9/83
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3915'
Show depth and thickness of all water, oil and gas formations. \$127.24

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	341.89'	none
				5 1/2"	3814.90'	2982'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom was already plugged off with 35 sacks cement to 3400'. Shot pipe at
3102' & 2982'. Pulled total of 132 joints. Plugged well with 3 hulls, 10
gel, 50 cement, 10 gel, 1 hull, plug, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of December, 19 83

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION
Irene Hovine
Notary Public.

DEC 16 1983
12-16-83
CONSERVATION DIVISION
Wichita, Kansas

LARIO OIL & GAS COMPANY
 Watkins-Smith Unit No. 1
 100' SW of Cen. SE NE SW Sec. 16-31S-11W
 Barber County, Kansas

Drilling Commenced: September 19, 1961
 Drilling Completed: October 1, 1961
 Well Completed: October 6, 1961
 Drilling Contractor: Capitt Drilling, Inc.
 Total Depth - 3915'
 I.P. - 14,000 M.C.F.

CASING RECORD:

8 5/8" 337.50 (o.a.) Set @ 341.89'
 Cem. 275 sacks
 5 1/2" 3835.23 (o.a.) Set @ 3814.90'
 Cem. w/ 100 sacks

<u>Formation</u>	<u>Depth</u>
Surface soil, sandy	36
Shells & sand	110
Red bed, sandy	230
Red bed & shells	570
Shale & shells	1665
Lime & shale	2085
Lime	2437
Shale & lime	3020
Lime	3124
Lime & shale	3915

GEOLOGICAL TOPS - R.B. MEAS.

	1741 Gr.	1751 K.B.
Elevation	3539	-1788
Base LeCompton	3586	-1835
Elgin Sandstone	3716	-1965
Heebner	3763	-2012
Douglas Sandstone	3840	-2089
Douglas Limestone	3852	-2101
Second Douglas Sandstone	3896	-2145
Lansing	3915	-2164
Rotary T.D.		

10-3-61 Welex perforated 16 holes 3764-3768'
 10-4-61 Dowell acidized with 500 gallons mud acid.

P.B. 3789

Approx top of emt @ 3198'

RECEIVED
 STATE CORPORATION COMMISSION

OCT 28 1983
 10-28-83
 CONSERVATION DIVISION
 Wichita, Kansas