


15-165-30096-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

RUSH County. Sec. 31 Twp. 16S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner JOHN O. FARMER, INC.
Lease Name USHER Well No. 1
Office Address Box 352, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) GAS
Date well completed October 12 1965
Application for plugging filed November 1974
Application for plugging approved November 4, 1974
Plugging commenced November 1, 1974
Plugging completed November 11, 1974
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Topeka Depth to top 3058' Bottom Total Depth of Well 3636 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None
				2-7/8"	3218'	355'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump in 40 sx. cement 3058-68 Pump plug to 2750'
Cut 2-1/2" casing @ 2680'. Spot mud and oil. (5 sx. Gel, 35 BBL. oil)
Let set 2 days. Casing stuck @ 350'. Pump in 3 sx. hulls, 3 sx. gel
1 1/5 Perforate @ 560'. Pump in 6 sx. gel and 25 bbls. oil
11/11 Pump in 40 sx. cement with 3% gel @ 560'. Cut casing @ 355'
Pump in 40 sx. cement @ 350'
Pump in 30 sx. cement @ 200'
Pump in 30 sx. and fill 8-5/8" to top with cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1974
CONSERVATION DIVISION
Wichita, Kansas
11-14-1974

Name of Plugging Contractor JOHN O. FARMER, INC. (If additional description is necessary, use BACK of this sheet)
Address Box 352, Russell, Kansas 67665

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
JOHN O. FARMER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer
Box 352, Russell, Kansas 67665 (Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 1974

My commission expires February 15, 1975
Helen Carlson Notary Public

