


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-145-00079-00-00

NORTH



Locate well correctly on above  
Section Plat

Rush County, Sec. 29 Twp. 16 Rge. 17 (E) (W)

Location as "NE/CNWSWK" or footage from lines. NE NE SW

Lease Owner: Aurora Gasoline Company

Lease Name: Lippert Well No. 1

Office Address: Union Natl Bank Bldg, Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-8 19 56

Application for plugging filed 4-8 19 56

Application for plugging approved 4-8 19 56

Plugging commenced 4-8 19 56

Plugging completed 4-8 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Box 283, Hoisington, Kas.

Producing formation Depth to top Bottom Total Depth of Well 3607 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	256'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole w/100 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Leben Drilling, Inc.

Address: 505 Orpheum Bldg, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

James M. Battin (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin

Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 13th day of April, 19 56

Lois D. Lissner

Notary Public.

My commission expires April 20, 1959

**PLUGGING**  
FILE SEC 29 T 16 R 17W  
BOOK PAGE 52 LINE 43

04-14-1954

15-154-00079-00-00

CONTRACTOR'S WELL LOG

COMPANY: Leben Drilling, Inc., and Aurora Gasoline Company  
 CONTRACTOR: Leben Drilling, Inc.  
 FARM: Lippert No. 1  
 LOCATION: NE NE SW Sec. 29-16-17, Rush County, Kansas  
 COMMENCED: March 28, 1956  
 COMPLETED: April 8, 1956

0	49	Surface soil
49	240	Shale
240	525	Shale, lime
525	780	Dakota Sand
780	786	Shale, lime
786	1121	Shale, redbed
1121	1158	Anhydrite
1158	1230	Shale, shells
1230	1485	Shale, lime, shells
1485	1759	Shale
1759	1930	Shale, lime
1930	2040	Lime, shale
2040	2330	Lime
2330	2590	Lime, shale
2590	2825	Shale, lime
2825	2869	Lime, shale
2869	2972	Lime
2972	3131	Lime, shale
3131	3200	Lime
3200	3295	Lime, shale
3295	3505	Lime
3505	3589	Lime, shale
3589	3607	Sand, shale
	<u>3607</u>	<u>Rotary Total Depth, D &amp; A</u>

Set 8 5/8" Surface Casing at 256 feet with 125 sacks cement.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lippert No. 1, NE NE SW Sec. 29-16-17, Rush County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: James M. Battin

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of April, 1956.

Lama A. Lison  
Notary Public

My commission expires April 20, 1956

**PLUGGING**  
FILE SEC. 29 T. 16 R. 17W  
BOOK PAGE 52 LINE 43

04-14-1956