

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25597-00-00  
Spot: SWSENESE Sec/Twnshp/Rge: 18-18S-25W  
1646 feet from S Section Line, 591 feet from E Section Line  
Lease Name: BLACK STONE Well #: 2  
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2013 1:30 AM  
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC  
Proposal Rcvd. from: JEREMY STUCKY Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 30 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 06/22/2013 3:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 540' WITH 30 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUL 05 2013

RECEIVED

District: 01

Signed Eric MacLaren  
7/19/13 (TECHNICIAN)

RECEIVED

JUL - 1 2013

KCC DODGE CITY