

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21186-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 27-15S-35W
1200 feet from S Section Line, 1480 feet from E Section Line
Lease Name: KEN BAKER B Well #: 27-1
County: LOGAN Total Vertical Depth: 4759 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	311		190 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/05/2013 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: GARY AXTEL Company: H2 DRILLING LLC Phone: (620) 290-5389

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 07/05/2013 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2450 w/25 sx
2nd plug @1250 w/100 sx
3rd plug @360 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: CONSOLIDATED

Plugged through: DP

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed Richard Williams
7/19/13 (TECHNICIAN)

cm

JUL 08 2013