

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24942-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 11-16S-11W
650 feet from N Section Line, 2000 feet from E Section Line
Lease Name: HOUSKA Well #: 2-11
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3377	1178	125 SX
SURF	8.625	455		240 SX
T1	2.375	3331		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2013 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: LEE BIEBERLE Company: SAMUEL GARY Phone: (620) 786-4601

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2013 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped off with 5 sx cement.
Cut casing at 1178'. Pulled casing to 1170' and pumped 125 sx cement w/300 # hulls.
Pulled casing to 750' and pumped 40 sx cement w/100 # hulls.
Pulled casing to 450' and pumped 40 sx cement.
Pulled casing to 200'. Circulated cement to surface with 40 sx cement.
Pulled casing. Topped of with 15 sx cement.

GPS: 38.67974 -098.50511

Perfs:

Top	Bot	Thru	Comments
3283	3285		
3276	3279		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA

JUL 08 2013

RECEIVED

District: 04

Signed Bruce Rodie
7/19/13 (TECHNICIAN)

CM

SUN 26 2013