

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25637-00-00
Spot: NENWNESE Sec/Twnshp/Rge: 20-17S-13W
2580 feet from S Section Line, 940 feet from E Section Line
Lease Name: SH UNIT Well #: 1-20
County: BARTON Total Vertical Depth: 3527 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 445 UNION BOULEVARD SUITE 208
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3515	1688	150 SX
SURF	8.625	947		350 SX
T1	2.375	3460		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2013 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES LLC Phone: (785) 623-1524

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Set CIBP over perforations and topped with 4 sx cement.
Cut casing at 1688'. Pulled casing to 1500' and pumped 120 sx cement w/300# hulls.
Pulled casing to 1000' and pumped 40 sx cement w/100 # hulls.
Pulled casing to 400'. Circulated cement to surface with 90 sx cement and 100 # hulls.
Pulled casing. Topped off with 10 sx cement.

GPS: 38.48392 -098.82309

Perfs:

Top	Bot	Thru	Comments
3434	3438		
3429	3436		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA

JUL 09 2013

RECEIVED

District: 04

Signed Bruce Rodie
7/19/13 (TECHNICIAN)

CM

JUN 27 2013