

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20611-00-00
Spot: NESENW Sec/Twnshp/Rge: 13-7S-17W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CASADA Well #: 1
County: ROOKS Total Vertical Depth: 3330 feet

Operator License No.: 30911
Op Name: SNEATH, GENE DBA LUCKY IRON
Address: 2060 17TH RD PO BOX 8
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	4.5	2807		275 SX
PROD	2.375	2500		0 SX
PROD	4.5	2807		
SURF	8.625	235		145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GENE SNEATH Company: LUCKY IRON Phone: (785) 434-4807

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2013 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2000' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1200' and pumped 80 sx cement w/200 # hulls to circulate cement to surface.
Pulled all tubing. Hooked to 4 1/2" casing and pumped 15 sx cement. Shut in pressure 300 psi.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 200 psi. Shut in pressure 200 psi.

Perfs:

Remarks: ALLIED TICKET # 56616

Plugged through: TBG

KCC WICHITA

JUL 09 2013

RECEIVED

District: 04

Signed

7/19/13

Pat Bedore

(TECHNICIAN)

CM

JUN 20 2013