

1 060388

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,733 -00-00
50' N of
NE NE NE , SEC. 15 ; T 16 S, R 17 W/X
4670 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5354

Lease Name Burgardt A Well # 8

Operator: Southern States Oil Co.

County Rush

Name & Address Box 1365

Well Total Depth 3667 119.18 feet

Great Bend, KS 67530

Conductor Pipe: Size 11-05-1084 feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 am Day: 31 Month: October Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3578' Perfs at 3294-2170'

1st plug sand back to 3120' and dump 4 sx cement on top of sand through bailer, Shoot pipe

2nd plug load hole with water and pump fluid to get rate of flow. Start cement & pump down 4 1/2" (85 to 100 sacks)

3rd plug pump cement down annulus until it pressures up.

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 am Day: 31 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3578' Perfs at 3294-2170'

1st plug sanded back to 3120' and dumped 4 sx cement on top of sand through bailer. Shot pipe off at 1080', 2nd plug loaded hole with water and pumped 2 barrels of fluid per minute at 750 psi. Started cement and pumped 97 sx down 4 1/2" Maximum pressure 950 psi and shut in pressure 750 psi. 3rd plug pumped 3 sx cement down annulus and pressured up.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun. No recovery

additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-17-84

INV. NO. 4668

Signed Paul A. Luthie
(TECHNICIAN)