

1060343

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,221-00-00

SW NE SW, SEC. 16; T 16 S, R 17 W  
1650 feet from N SE Corner of  
3630 feet from W SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Urban Q Well # 2

Operator: Frontier Oil Co.

County Rush

Name & Address 1720 Kansas State Bank Building

Well Total Depth 3580 116.35 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1136

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 24 Month: September Year: 1984

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3579 Perfs at 3272-75, 97-3300, 3338-41, 3431-34, 3449-53, 68-71

1st plug sand back to 3220 and dump 4 sx cement on top of sand through bailer

2nd plug 15 sx gel, 50 sx cement 10 sx gel and 150 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 24 Month: September Year: 1984

ACTUAL PLUGGING REPORT 4 1/2" set at 3579' Perfs at 3272-75, 97-3300, 3338-41, 3431-34, 3449-53, and 68-71.

1st plug sanded back to 3220' and dumped 4 sx cement on top of sand through bailer.

Shot off pipe and collar came off and pipe fell down hole 220' - could not retrieve it.

2nd plug pumped 15 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement.

Maximum pressure 600 psi and shut in pressure 500 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. (If additional description is necessary, use BACK of this form.)

OCT 01 1984  
10-01-1984

INVOICED

DATE 10-8-84

INV. NO. 4120

Signed Paul A. Luthie (TECHNICIAN)