

1030751

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW/4 NE/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-15-165-20671-00-00
SEC. 15, T 16 S, R 17 W/EX
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678
Operator: Lasmo Energy Corporation
Name & Address P.O. Box 1365
Great Bend, KS 67530

Lease Name Burgardt "A" Well # 7
County Rush 118.04
Well Total Depth 3632 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1179

Abandoned Oil Well _____ Gas Well _____ Input Well _____ INJ. Well _____ SMD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 29 Month: 10 Year: 1986

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-659-3165

were: 4 1/2" at 3631' Perfs at 3468-74', 3486-92', 3448-54', 3354-62' Elevation 2015' KB

1st plug sand back to 3275' and dump 4 sx cement on top of sand through bailer.

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" plug and pump 120 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 10 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3275 and dumped 4 sx cement on top of sand
through bailer.

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx
hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

Maximum pressure 900 psi and shut in 100 psi.

Remarks: Recovered 1860' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. 11-04-1986
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Steve Shumant
(TECHNICIAN)

DATE 11-4-86

INV. NO. 15296
10-29