

1 070905

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS, 67202

1-9
API NUMBER 15-165-20,981-00-00
150' E of
C NW SW, SEC. 16, T 16 S, R 17 W/E
1980 feet from S section line
4470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456
Operator: A F G Energy, Inc.
Name & Address: P.O. Box 605
Russell, KS 67665

Lease Name Urban "Q" Well # 3
County Rush
Well Total Depth 3585 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1131

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 9 Month: 1 Year: 19 91

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were 4 1/2" at 3583' w/150 sx cement, CIBP 3236'. Perfs at 3018-3191'
1st plug sand back to 2960' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:45 p.m. Day: 9 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 2975' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement down 8 5/8".
Maximum pressure 900 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 2-8-91
INV. NO. 30614

Signed Dan Jordan (TECHNICIAN)