

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-28898-00-00
Spot: SWNENW Sec/Twnshp/Rge: 35-25S-18E
1155 feet from N Section Line, 1423 feet from W Section Line
Lease/Unit Name: H&A BARNETT Well Number: 7
County: ALLEN Total Vertical Depth: 980 feet

Operator License No.: 8282
Op Name: BARNETT, HAROLD LEON
Address: 651 1600 ST.
HUMBOLDT, KS 66748

Conductor Pipe: Size _____ feet:
Surface Casing: Size 7 feet: 21 5 SX CMT \$35.00
Production: Size _____ feet:
Liner: Size _____ feet:

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/06/2001 8:00 AM
Plug Co. License No.: 6137 Plug Co. Name: ENSMINGER, DONALD & JACK
Proposal Rcvd. from: DAVID KINSEY Company: ENSMINGER, DONALD & JACK Phone: (316) 473-2473

Proposed Plugging Method: This well consisted of an uncased bore to 980'. The plugging proposal was to place a 50' cement plug at 975', a 50' cement plug at 500' and a continuous cement plug from 250' to surface.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 04/06/2001 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
1" pipe was ran into the well to 975'. The well was gelled for bridging purposes. 10 sacks of cement were pumped through the 1" pipe to 975'. The 1" pipe was pulled to 500' and 10 sacks of cement were pumped to that depth. The 1" pipe was pulled to 250'. Cement was pumped into the 1" pipe until cement circulated from the 7" surface casing at surface. The 1" pipe was removed. Displacement was filled from surface. 60 sacks of cement were pumped into this well.

INVOICED
DATE 5-7-01
WELL NO. 2001061766
RECEIVED
KCC District #3
MAY 3 2001
Chanute, KS

STATE CORPORATION COMMISSION

Remarks: _____
Plugged through: _____
MAY 7 2001
CONSERVATION DIVISION

District: 03 Signed Clayton P. Titel by SK
(TECHNICIAN)