

LEASE NAME Hoofer

WELL NUMBER #1

4290' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 19 TWP. 16S RGE. 17 (E) or (W)

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR TENGASCO, INC.

ADDRESS P.O. Box 458 Hays, Kansas 67601-0458

COUNTY Rush

PHONE# (785) 625-6374 OPERATORS LICENSE NO. 32278

Date Well Completed 12-08-1966

Character of Well GAS

Plugging Commenced 01-24-2001

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 01-24-2001

The plugging proposal was approved on 01-10-2001 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation LKC Depth to Top 3248' Bottom 3445' T.O. 3488'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	gas & water	surface	220	8.625"	08-24-66	NONE
		surface	3525'	4.5"	09-04-66	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pumped 30 sacks cement & 150#'s hulls through tubing at 3100 feet. Pulled tubing up to 1100' & circulated 75 sacks & 200#'s hulls to surface. Pulled tubing and pumped 20 sacks down 4.5" casing. Pumped 15 sx. down backside.

Name of Plugging Contractor ALLIED CEMENTING License No. RECEIVED

Address Russell, Kansas 67665 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TENGASCO, INC. FEB - 8 2001

STATE OF _____ COUNTY OF _____, ss. 02-08-2001

Ed Glassman (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ed Glassman

(Address) P.O. Box 458 Hays KS 67601

SUBSCRIBED AND SWORN TO before me this 2nd day of Feb, 2001

Prada K. Fernandez
 Notary Public

My Commission Expires: 2/15/2004

af