

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-165-00359 000

LEASE NAME Lippert

WELL NUMBER #2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650' Ft. from S Section Line  
330' Ft. from E Section Line

SEC. 19 TWP. 16S RGE. 17 (E) or (W)

COUNTY Rush

Date Well Completed 08-01-1963

Plugging Commenced 01-22-2001

Plugging Completed 01-23-2001

LEASE OPERATOR TENGASCO, INC.

ADDRESS P.O.Box 458 Hays, Kansas 67601-0458

PHONE/(785) 625-6374 OPERATORS LICENSE NO. 32278

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-12-2001 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation Plattsmouth Depth to Top 3172' Bottom 3180' T.O. 3515'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 8 2001

02-08-2001

CONSERVATION DIVISION  
Wichita Kansas

Formation	Content	From	To	Size	Put in	Pulled out
Plattsmouth	gas & water	surface	222'	8.625"	05-10-63	NONE
LKC	gas & water	surface	3517'	5.5"	05-19-63	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Pumped 5 sacks cement down backside. Pumped 25 sacks cement & 100 #'s hulls at 3031'. Pulled tubing to 1100 feet. Pumped 170 sacks cement & 200 #'s hulls. Did not circulate to surface. Set CIBP at 1100 feet. Pumped 120 sacks cement to surface. Pumped 10 sacks cement down 5.5" casing.

Name of Plugging Contractor ALLIED CEMENTING License No. \_\_\_\_\_

Address Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TENGASCO, INC.

STATE OF KS COUNTY OF ELLIS, ss.

Ed Glassman

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) E Glassman

(Address) P.O. Box 458 Hays KS 67601

SUBSCRIBED AND SWORN TO before me this 7<sup>th</sup> day of Feb, 2001

Linda K. Pfannenstiel  
Notary Public

215/2004



af