

15-165-20046-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 18 Twp. 16S Rge. 17W (E) (WX)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Frontier Oil Company

Lease Name Legleiter Well No. 1

Office Address 1720 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed July 25 19 67

Application for plugging filed July 25 19 67

Application for plugging approved July 25 19 67


Plugging commenced July 25 19 67

Plugging completed July 25 19 67

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Depth to top Bottom Total Depth of Well 3535 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1090*	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Run Pipe in hole. Lay down DP to fill hole w/mud to 400*. Plug & 25 sx cement. Mud to 40. Plug & 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1967
07-28-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address Box 173, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Maxine V. Starr (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr

1720 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 67

Betty M. Maloney Notary Public.

My commission expires 3-22-71

15-145-20046-00-00

DRILLERS LOG

Legleiter No. 1

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 1090'	CONTRACTOR:	Red Tiger Drilling Co.	SW SW SW
w/225 sx cement	COMMENCED:	July 15, 1967	18-16S-17W
	COMPLETED:	July 25, 1967	Rush County, Ks.
			ELEVATION: 1968 DF
TOTAL DEPTH: 3535'			1971 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Post Rock	0	40	
Shale, Rock & Sand	40	110	
Shale	110	520	
Sand	520	730	
Shale	730	1084	
Anhydrite	1084	1124	
Shale	1124	1840	
Shale & Lime	1840	2125	
Lime	2125	2300	
Shale & Lime	2300	2984	
Lime	2984	3197	
Heebner Shale	3197	3201	
Lime & Shale	3201	3266	
Lime	3266	3505	
Conglomerate	3505	3535	

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1967
 07-28-1967
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 27th day of July, 1967.

Betty M. Maloney
 Notary Public

My Commission Expires:

3-22-71