

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21805-0000

LEASE NAME Massey "A"

WELL NUMBER 1-29

1,650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 29 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 10-12-02

Plugging Commenced 10-12-02

Plugging Completed 10-12-02

RECEIVED
10-18-02
OCT 18 2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 S. Main, Ste 200, Wichita, KS 67202

PHONE#(316) 262-2596 OPERATORS LICENSE NO. 9408

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-12-02 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	234'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push bridge plug to 2,170', spot 50 sax cement on plug; push bridge plug to 1,400', spot 50 sax cement on plug; push bridge plug to 250', spot 50 sax cement on plug; push wiper plug to 40' dump 15 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 15th day of October, 2002

My Commission Expires: _____

Keith Phillips
Notary Public




Shields

Russell, Kansas

WELL LOG

Operator: Trans Pacific Oil Corp.
 Well: Massey "A" #1-29
 Commenced: September 30, 2002
 Completed: October 12, 2002
 Contractor: Shields Drilling Co.

Well Description: SE NE SE
 Sec. 29-16S-27W
 Lane Co., KS



CASING RECORD

Size	Run	Pulled
8 5/8"	234'	Cmtd. w/160 sax

Elevation: 2,714' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale & sand	2,131'
Anhydrite	2,164'
Shale	3,581'
Shale & lime	4,074'
Lime	4,171'
Lime & shale	4,201'
Lime	4,283'
Lime & shale	4,356'
Lime	4,408'
Lime & shale	4,484'
Lime	4,640' RTD

Notes